



UNREINFORCED CONCRETE  
OPTION

Notes:

1. Refer to Auckland City Council Standard Engineering Details for concrete footpath construction notes.
2. Undercutting and Basecourse/Bedding Layer depth to be increased for weak subgrades (CBR <3).
3. During Maintenance Works a minimum of three 1m panels of footpath must be replaced.
4. The surface shall be sprayed with Rugisol C or similar prior to curing and then cleaned.
5. This detail only applies to Mt. Wellington Quarry Code of Subdivision

PREPARED BY OPUS:



**AUCKLAND CITY**  
Transport

MT WELLINGTON QUARRY  
INSITU CONCRETE FOOTPATH

SCALE : NTS

DRAWN : JWF

ISSUE DATE : 11/2008

APPROVED :

PLAN No. 2008/1301  
ISSUE B