



## NOTES:

## STEELWORK

1. ALL STEEL SECTIONS AND PLATES SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF NZS/AS 3678 AND NZS/AS 3679 OR APPROVED EQUIVALENT.

## CONCRETE

1. CONCRETE TO BE 25 MPA AT 28 DAYS.
2. CONCRETE FINISH TO BE U3 AS DEFINED IN NZS 3114.
3. CONCRETE TO BE IN ACCORDANCE WITH NZS 3104 AND CONCRETE CONSTRUCTION TO BE IN ACCORDANCE WITH NZS 3109.



DETAIL:

## GUARD RAIL : STEEL POST

Engineering  
Quality  
Standards

DETAIL No:

R26

**MANUKAU CITY COUNCIL**

UPDATED:

FEB 2007